CHITALDRUG DISTRICT.

Notification dated 16th April 1937.

It is hereby notified that a sum of Rs. 2-8-0 being the Commission due to Ex-Patel Shivalingappa of Chickandavadi in Holalkere Range, for June 1936, is lying unclaimed with the Range Forest Officer, Holalkere. If the amount is not claimed by the heirs of the deceased with necessary certificate, within two months, the same will be forfeited to Government and further claim that may be preferred will be rejected thereafter.

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice dated 11th April 1937.

The attention of the public is invited to the notification calling for tenders for the labour portion of the work for "Improving water supply to Chickmagalur Town," published in Part VI, pages 536-537 of the *Mysore Gazette*, dated 15th April 1937.

The last date for receiving tenders is fixed on 3rd May 1937.

Notification dated 21st April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 17th May 1937, for constructing Masonry Reservoir and Suction Well, etc., for Water Supply to Saklespur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office, between the hours of 11 A.M. and 5 P.M on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing Masonry Reservoir and Suction Well, etc., for Water Supply to Saklespur Town," in default of which, the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Approximate estimate of quantities of work of constructing masonry reservoir and suction well, etc., for water supply to Saklespur Town.

No.	Particulars	Unit	Quantity
	CONSTRUCTING MASONRY RESERVOIR.		
1	(*a*) Earthwork excavating foundation in ordinary soil up to 3′ depth	C.yd.	90
	(*b*) Do in gravelly soil from 3 to 5 feet depth ..	,,	81
2	Burnt stone jelly concrete in surki mortar	C.ft.	1,015
3	Cement concrete 1 : 2 : 4	,,	120
4	Burnt brick in surki mortar	,,	1,919
5	Cement plastering $\frac{1}{2}$″ thick	Sqr.	20·47
6	Rolled steel girders including hoisting and fixing	Cwt.	4·71
7	Burnt stone slabs roughly dressed and fixed 4$\frac{1}{2}$″ to 6″ thick ..	S.ft.	51
8	Reinforced cement concrete roofing 6″ thick complete	Sqr.	4·95
9	Constructing parapet walls with burnt brick in chunam as per design	R.ft.	86
10	Cornice 9″ thick with burnt brick in chunam plastering, etc., complete	,,	89
11	Providing and fixing iron ladder	,,	20
12	Providing and fixing manhole wrought iron frame and cover 2$\frac{1}{2}$′ × 2$\frac{1}{2}$′	No.	4
13	Constructing sluice valve cisterns as per type design	,,	4
	CONSTRUCTING SUCTION WELL 8′ DIA. 20′ DEEP.		
1	(*a*) Earthwork excavation in 1st fathom	C.yd.	13
	(*b*) Do 2nd fathom	,,	13
	(*c*) Do 3rd fathom	,,	13
	(*d*) Do 4th fathom	,,	4
2	Staining with reinforced cement concrete curbs 4″ thick	C.ft.	205
3	Size stone in surki mortar for parapet wall	,,	33
4	Cement pointing to stone walls	Sqr.	1·49
5	Providing iron ladder	R.ft.	24
6	Providing iron grating with expanded metal and locking arrangement, etc., complete on the top of well	S.ft.	71
	DRAW OFF ARRANGEMENT.		
1	Earthwork excavation for jelly duct	C.yd.	703
2	Laying and lead jointing 8″ C.I. pipe including cutting wherever necessary	No.	15
3	Rough stone rivetment including jelly packing	C.yd.	105
4	Filling with rough stone and jelly	,,	133
5	Constructing valve cistern as per type design	No.	
6	Carting 8″ C.I. pipe from Hassan to Saklespur and laying along the draw off line	Cwt.	

Notification dated 21st April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanit
neer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 17th May 1937, f
portion of work for Laying Pipe line for Water Supply to Saklespur Town. An a
estimate of quantities is given below. These quantities are not guaranteed. The wor
completed by the end of June 1937.

2. The plans and conditions may be seen at the Sanitary Engineer's Office,
hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained fro
Engineer. The tenders should be accompanied by a statement in the form given
the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash (no
accepted) as earnest money, and be superscribed "Tender for labour po
laying pipe lines for Water Supply to Saklespur Town" in default of which th
rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Estimate of the approximate quantities for labour portion of the work of laying pipe lines for Water Supply to Saklespur Town.

No.	Particulars	Unit	Quantity
1	Constructing public platforms as per type design	No.	30
2	Earthwork excavating pipe trench for laying 5″ C.I. pipes	C.yd.	489
3	Laying and lead jointing 5″ C.I. pipes with cuts wherever necessary.	No.	100
4	Do 4″ C.I. pipes do	,,	434
5	Do 3″ do do	,,	200
6	Laying and jointing 2″ G.I. pipe including cuts and threads with earthwork, etc., complete	R.ft.	4,220
7	Do $1\frac{1}{2}$″ G.I. pipes	,,	8,760
8	Do 1″ do	,,	1,300
9	Do $\frac{3}{4}$″ do	,,	1,200
10	Constructing valve cisterns as per type design	No.	3
11	Constructing gland cock cisterns $1\frac{1}{2}' \times 1\frac{1}{2}' \times 2'$ as per type design ..	,,	35
12	Carting from Hassan to Saklespur 5″×4″×3″ C.I. pipes and laying along the rising and distribution mains	Cwt.	136

B. R. GARUDACHAR,
Sanitary Engineer.

BUILDINGS DIVISION, BANGALORE.

Notification dated 29th April 1937.

tice is hereby given that sealed tenders will be received up to 2 P.M. of 10th May 1937 at the the Executive Engineer, Buildings Division, Bangalore, for "Running a Hindu Restaurant v Building near the Band Stand in Cubbon Park", Bangalore, for one year from 1st June

e period may be extended to three years at the discretion of Government on the basis of being given by the lessee.

ers should be accompanied by an earnest money deposit of Rs. 200 (Two Hundred nd should be superscribed "Tenders for running a Hindu Restaurant in the new bbon Park", Bangalore.

nthly rate of rent offered should be written both in words and figures and the same ays in advance before the 5th of each month.

in payment of rent will be countenanced. Default in payment will involve can- ct and forfieture of earnest money deposit.

ns shall be effected in the Building without obtaining the permission of proper l. The club and its surroundings shall be kept neat and tidy. The proprietor or all the electrical and other fittings in the Building.

7. He will provide his own stock of decent furniture. Pay his own light (Electric), water and sanitary cess bills, etc.

8. The right of running the club shall not be transferred.

9. The acceptance of tender rests with the Superintending Engineer, Mysore Circle, who will have the power to reject or to accept any tender without assigning reasons. His order will be final and binding on all tenderers.

10. The name of the successful tenderer will be put on Notice Board by the 3rd week of May 1937 and the earnest money of the unsuccessful tenderer will be returned on application.

11. Provision is made in the kitchen for drawing electric power for electric cooking ranges to be installed by the tenderer. There is an ordinary chimney erected also for ordinary ovens. The tenderer is to put the necessary platforms and lead the smoke to chimney. The building shall not be used for dwelling purposes.

12. The proprietor will employ properly clothed and trained attendants. At least one head server having experience in the Restaurants run on western lines to keep everything neat and tidy will have to be employed. The quipment of curniture, etc., will be on lines approved by Government installing a Radio set is also necessary.

13. The Building under reference is now fetching a rent of Rs. 310 per mensem.

14. For further particulars the Executive Engineer will be glad to furnish any information that may be required by the intending tenderers.

N. KRISHNIENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, KOLAR DIVISION.

Auction sale of the P. W. D. Sub-Division Officers Quarters at Bowringpet.

1. The above building with its out houses, compound measuring 165′×80′ as per plan available for inspection in the Executive Engineer's Office, Kolar and the Sub-Division Office, Bowringpet, will be sold by public auction on 17th May 1937, between 9 A.M. and 11 A.M. by the Executive Engineer, Kolar Division, or his representative at the premises.

2. Intending bidder will have to deposit a sum of Rs. 50 (Fifty only) before the commencement of the auction sale, which will be refunded after the sale is over.

3. The building will be knocked down to the highest bidder who will have to pay in full the sale money immediately.

4. The sale is subject to confirmation by the Superintending Engineer. If the successful bidder fails to pay the sale money on the spot immediately the property will be resold at the risk and the cost of the defaulting bidder whose deposit also is subject to forfeiture in addition. He has however no right over the profits if any.

5. The possession of the building will be made over after the sale is confirmed by the Superintending Engineer, of which the bidder will be informed in due course.

P. RAJAGOPALAN,
Executive Engineer.

MEDICAL DEPARTMENT

OFFICE OF THE SUPERINTENDENT, GOVERNMENT MEDICAL STORES, BANGALORE CITY.

Notification, dated 18th March 1937.

Notice is hereby given that the undermentioned unserviceable articles will be sold by public auction at 1 P.M. on Wednesday the 5th May 1937, in the premises of the Medical Stores.

The full amount of the bid must be paid immediately and the things removed then and there.